


NATIONAL DAM INSPECTION PROGRAM UPPER ANSONIA RESERVOIR 1/1  
DAM (CT 00029) HO..(U) CORPS OF ENGINEERS WALTHAM MA  
NEW ENGLAND DIV SEP 80

F/G 13/13 NL

END  
DATE  
FILMED  
8-84  
DTIC




MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

DTIC

AD-A142 594

HOUSATONIC RIVER BASIN  
DERBY, CONNECTICUT  
**UPPER ANSONIA RESERVOIR DAM**  
**CT 00029**

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

DTIC FILE COPY

SEPTEMBER, 1980

This document has been approved  
for public release and sale; its  
distribution is unlimited.

84 06 29 066

**HOUSATONIC RIVER BASIN  
DERBY, CONNECTICUT  
UPPER ANSONIA RESERVOIR DAM  
CT 00029**

**PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM**



JUL 2 1984

A

**DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154**

**SEPTEMBER, 1980**

This document has been approved  
for public release and sale; its  
distribution is unlimited.

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CT 00029	2. GOVT ACCESSION NO. <b>A142594</b>	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Housatonic River Basin Derby, Conn., Upper Ansonia Reservoir Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE Sept. 1980
		13. NUMBER OF PAGES 75
		15. SECURITY CLASS. (of this report)  UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Housatonic River Basin, Derby Conn. <del>XXXX</del> Ansonia Reservoir Dam		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The Upper Ansonia Reservoir Dam was built around 1887 and presently impounds a water supply reservoir. The "Main Dam" is a masonry gravity structure with a total length of approx. 345 ft., including a 20.5 ft. long spillway and a masonry intake structure. The top of the masonry dam, at elevation 309.7, is 2.7 ft above the spillway crest, 20.8 ft. above the streambed at the downstream toe of the dam, and varies in width from 3 to 4.5 ft. A bedrock outcrop separates a 200 ft. long masonry and earth dike from left end of the Main Dam and separated from the dike by a small knoll is the "East Dam", which consists of a masonry gravity upstream wall and a downstream embankment.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

BRIEF ASSESSMENT  
PHASE I INSPECTION REPORT  
NATIONAL PROGRAM OF INSPECTION OF DAMS

Name of Dam:	UPPER ANSONIA RESERVOIR DAM
Inventory Number	CT 00029
State:	CONNECTICUT
County:	NEW HAVEN
Town:	DERBY
Stream:	TRIBUTARY TO NAUGATUCK RIVER
Owner:	ANSONIA-DERBY WATER COMPANY
Date of Inspection:	AUGUST 8, 1980
Inspection Team:	PETER HEYNEN, P.E.
	HECTOR MORENO, P.E.
	THEODORE STEVENS
	ROBERT JAHN


The Upper Ansonia Reservoir Dam was built around 1887 and presently impounds a water supply reservoir. As shown on Sheets B-1 to B-3, it consists of a masonry gravity dam, a masonry and earth dam and a masonry and earth dike. The "Main Dam" is a masonry gravity structure with a total length of approximately 345 feet, including a 20.5 foot long spillway and a masonry intake structure. The top of the masonry dam, at elevation 309.7 (NGVD), is 2.7 feet above the spillway crest, 20.8 feet above the streambed at the downstream toe of the dam, and varies in width from 3 to 4.5 feet. A bedrock outcrop separates a 200 foot long masonry and earth dike from the left end of the Main Dam. The dike has a top elevation of 309.5 and is approximately 7 feet high. Approximately 700 feet left of the Main Dam and separated from the dike by a small knoll is the "East Dam", (See Sheet B-1), which consists of a masonry gravity upstream wall and a downstream embankment. The East Dam has a total length of approximately 423 feet, consisting of two sections separated by a low bedrock outcrop which rises to within 5 feet of the top of the dam. The left section is 227 feet in length and 16.2 feet in height and the right section is 196 feet in length and 11 feet in height. The East Dam has a top elevation of 310.0, a top width of 4 to 4.8 feet and does not have a spillway. With the reservoir level to the top of the project, the reservoir impounds approximately 310 acre-feet of water.

In accordance with U.S. Army Corps of Engineers Guidelines, Upper Ansonia Reservoir Dam is classified as a high hazard, small size dam. The test flood for the project is equivalent to the Probable Maximum Flood (PMF). peak inflow to the reservoir at test flood is 1,200 cubic feet per second (cfs); peak outflow is 870 cfs with the low point of the dike overtopped by 0.6 feet and the dam by 0.4 feet. The spillway capacity with the reservoir level to the lowest point along the top of the dike is 240 cfs, which is equivalent to 28% of the routed test flood outflow.


Based upon the visual inspection at the site and past performance, the project is judged to be in fair condition. No evidence of instability of the project was observed. However, there are items which require attention, such as seepage, trees and brush on and at the toe of the dam and dike, and deterioration of the masonry intake structure.

It is recommended that the owner retain the services of a registered professional engineer to perform a more detailed hydraulic/hydrologic analysis of the adequacy of the existing project discharge. Other items of importance are monitoring of seepage, removal of trees and brush and repair of the masonry intake structure.

The above recommendations and further remedial measures presented in Section 7 should be instituted within one year of the owner's receipt of this report.


  
Peter M. Heynen, P.E.

Project Manager - Geotechnical  
Cahn Engineers, Inc.



  
C. Michael Horton, P.E.

Chief Engineer  
Cahn Engineers, Inc.



A1

This Phase I Inspection Report on Upper Ansonia Reservoir Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

ARAMAST MAHTESIAN, Member  
Geotechnical Engineering Branch  
Engineering Division

CARNEY M. TERZIAN, Member  
Design Branch  
Engineering Division

RICHARD DIBUONO, Chairman  
Water Control Branch  
Engineering Division

APPROVAL RECOMMENDED:

JOE B. FRYAR  
Chief, Engineering Division



## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspection. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam would necessarily represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions will be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

I

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

The information contained in this report is based on the limited investigation described above and is not warranted to indicate the actual condition of the dam. The integrity of the dam can only be determined by a means of a monitoring program and/or a detailed physical investigation. The accuracy of available data is assumed where not in obvious conflict with facts observable during the visual inspection.

## TABLE OF CONTENTS

	<u>Page</u>
Letter of Transmittal	
Brief Assessment	i, ii
Review Board Signature Page	iii
Preface	iv, v
Table of Contents	vi-viii
Overview Photo	ix
Location Map	x

### SECTION 1: PROJECT INFORMATION

1.1 <u>General</u> .....	1-1
a. Authority	
b. Purpose of Inspection Program	
c. Scope of Inspection Program	
1.2 <u>Description of Project</u> .....	1-2
a. Location	
b. Description of Dam and Appurtenances	
c. Size Classification	
d. Hazard Classification	
e. Ownership	
f. Operator	
g. Purpose of Dam	
h. Design and Construction History	
i. Normal Operational Procedures	
1.3 <u>Pertinent Data</u> .....	1-3
a. Drainage Area	
b. Discharge at Damsite	
c. Elevations	
d. Reservoir Length	
e. Reservoir Storage	
f. Reservoir Surface	
g. Dam	
h. Diversion and Regulating Tunnel	
i. Spillway	
j. Regulating Outlets	

### SECTION 2: ENGINEERING DATA

2.1 <u>Design Data</u> .....	2-1
2.2 <u>Construction Data</u> .....	2-1
2.3 <u>Operations Data</u> .....	2-1

2.4	<u>Evaluation of Data</u> .....	2-1
	a. Availability	
	b. Adequacy	
	c. Validity	
SECTION 3: VISUAL INSPECTION		
3.1	<u>Findings</u> .....	3-1
	a. General	
	b. Dam	
	c. Appurtenant Structures	
	d. Reservoir Area	
	e. Downstream Channel	
3.2	<u>Evaluation</u> .....	3-3
SECTION 4: OPERATIONAL AND MAINTENANCE PROCEDURES		
4.1	<u>Operational Procedures</u> .....	4-1
	a. General	
	b. Description of Any Warning System In Effect	
4.2	<u>Maintenance Procedures</u> .....	4-1
	a. General	
	b. Operating Facilities	
4.3	<u>Evaluation</u> .....	4-1
SECTION 5: EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES		
5.1	<u>General</u> .....	5-1
5.2	<u>Design Data</u> .....	5-1
5.3	<u>Experience Data</u> .....	5-1
5.4	<u>Visual Observations</u> .....	5-1
5.5	<u>Test Flood Analysis</u> .....	5-1
5.6	<u>Dam Failure Analysis</u> .....	5-2
SECTION 6: EVALUATION OF STRUCTURAL STABILITY		
6.1	<u>Visual Observations</u> .....	6-1
6.2	<u>Design and Construction Data</u> .....	6-1
6.3	<u>Post Construction Changes</u> .....	6-1
6.4	<u>Seismic Stability</u> .....	6-1

## SECTION 7: ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES

7.1	<u>Dam Assessment</u> .....	7-1
	a. Condition	
	b. Adequacy of Information	
	c. Urgency	
7.2	<u>Recommendations</u> .....	7-1
7.3	<u>Remedial Measures</u> .....	7-1
	a. Operation and Maintenance Procedures	
7.4	<u>Alternatives</u> .....	7-2


## APPENDICES

	<u>Page</u>
APPENDIX A: <u>INSPECTION CHECKLIST</u>	A-1 A-6
APPENDIX B: <u>ENGINEERING DATA AND CORRESPONDENCE</u>	
Project Location Plan	Sheet F-1
Main Dam-Plan, Profile and Sections	Sheet J-2
East Dam and Dike - Profiles	Sheet B-3
List of Existing Plans	B-1
Summary of Data and Correspondence	B-2
Data and Correspondence	B-3, B-4
APPENDIX C: <u>DETAIL PHOTOGRAPHS</u>	
Photograph Location Plan	Sheet C-1
Photographs	C-1 to C-4
APPENDIX D: <u>HYDRAULIC/HYDROLOGIC COMPUTATIONS</u>	
Drainage Area Map	Sheet D-1
Computations	D-1 to D-14
Preliminary Guidance for Estimating Maximum Probable Discharges	i to viii
APPENDIX E: <u>INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS</u>	E-1



OVERVIEW PHOTO  
(August, 1980)

US ARMY ENGINEER DISTRICT NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS	NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS	Upper Ansonia Res. Dam Tr-Naugatuck River	Derby CONNECTICUT	DATE Sept. '80 CE # 27 785 KC PAGE 1A
CAHN ENGINEERS INC WALLINGFORD, CONN ENGINEER				



PHASE I INSPECTION REPORT  
UPPER ANSONIA RESERVOIR DAM  
SECTION I - PROJECT INFORMATION

1.1 GENERAL

a. Authority - Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Cahn Engineers, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed were issued to Cahn Engineers, Inc. under a letter of April 14, 1980 from William E. Hodgson, Jr., Colonel, Corps of Engineers. Contract No. DACW 33-80-C-0052 has been assigned by the Corps of Engineers for this work.

b. Purpose of Inspection Program - The purposes of the program are to:

1. Perform technical inspection and evaluation of non-federal dams to identify conditions requiring correction in a timely manner by non-federal interests.
2. Encourage and prepare the States to quickly initiate effective dam inspection programs for non-federal dam.
3. To update, verify and complete the National Inventory of Dams.

c. Scope of Inspection Program - The scope of this Phase I inspection report includes:

1. Gathering, reviewing and presenting all available data as can be obtained from the owners, previous owners, the state and other associated parties.
2. A field inspection of the facility detailing the visual condition of the dam, embankments and appurtenant structures.
3. Computations concerning the hydraulics and hydrology of the facility and its relationship to the calculated flood through the existing spillway.
4. An assessment of the condition of the facility and corrective measures required.

It should be noted that this report does not pass judgement on the safety or stability of the dam other than on a visual basis. The inspection is to identify those features of the dam which need corrective action and/or further study.



## 1.2 DESCRIPTION OF PROJECT

a. Location - The Upper Ansonia Reservoir Dam is located on an unnamed tributary to the Naugatuck River in the Housatonic River Basin in a suburban area of the Town of Derby, County of New Haven, State of Connecticut. The dam is shown on the Ansonia USGS Quadrangle Map, having coordinates latitude N41°19.2' and longitude W73°04.4'. The Lower Ansonia Reservoir is located approximately 550 feet downstream.

b. Description of Dam and Appurtenances - As shown on Sheets B-1 through B-3, the project consists of the 345 foot long Main Dam, the 423 foot long East Dam, and a 200 foot long dike to the left of the Main Dam.

The Main Dam, shown on Sheet B-2, is a 20.8 foot high masonry gravity structure and contains a 20.5 foot long spillway and the outlet facilities for the project. According to existing drawings, the dam was raised approximately 5 feet by addition of masonry to the downstream face of an old masonry dam. The old dam, with an approximate top elevation of 305, has an earth embankment on its upstream side. The upstream face of the portion of the present dam rising above the old dam is at a batter of approximately 1 horizontal to 4 vertical. In the area of the spillway, where the dam reaches its greatest height, the downstream face is tiered, with each tier having a batter of approximately 1 horizontal to 9 vertical. The entire dam appears to be founded on bedrock, except for a 116 foot long section at the right end. This section of the dam has embankments upstream and downstream of the masonry wall.

A bedrock outcrop separates the left end of the dam from a 200 foot long, 7 foot high dike which consists of an upstream masonry wall and a downstream earth embankment. The dike appears to be founded on bedrock and has a vertical upstream face, a top width of about 25 feet and a downstream slope inclined at approximately 4 horizontal to 1 vertical.

The 423 foot long East Dam appears to be founded on bedrock and consists of a masonry wall with an earth embankment on its downstream side. The wall has a vertical upstream face and an approximate top elevation of 310. The embankment has an approximate top elevation of 307, a top width of about 10 feet and a downstream slope inclined at approximately 2 horizontal to 1 vertical. A low bedrock ridge, rising to approximate elevation 305, separates the East Dam into a 227 foot long, 16.2 foot high left section and a 196 foot long, 11 foot high right section. Profiles of the dike and East Dam are shown on Sheet B-3.

The masonry intake structure for the project is located to the right of the spillway and approximately 15 feet from the upstream face of the Main Dam. The structure is not accessible from the dam, due to the condition of the service bridge, but appears to contain control mechanisms to a 12 inch cast iron low-level outlet and a 12 inch supply pipe which is gated to either feed into the Lower Reservoir or bypass the Lower Reservoir and feed directly to a chlorination house. The approximate invert elevations of the low-level outlet and the supply pipe are 290 and 295, respectively.

c. Size Classification - (SMALL) - The project is 20.8 feet in height and with the reservoir level to the top of the dam, impounds approximately 310 acre-feet of water. According to recommended guidelines, a dam with this maximum storage is classified as small in size.

d. Hazard Classification - (HIGH) - If the dam were breached, there is potential for loss of more than a few lives and extensive property damage in an urban area of Derby approximately 3000 feet downstream of the dam.

e. Ownership - Ansonia-Derby Water Company  
230 Beaver Street  
Ansonia, Connecticut 06401  
Mr. Fredrick Elliott (Superintendent)  
(203) 735-1888 (Work)  
(203) 734-0288 (Home)

The dam was built and owned by the now defunct Birmingham Water Company and acquired by the present owner around 1970.

f. Operator - Mr. William Clark (203) 734-6641

g. Purpose of Dam - The dam impounds a public water supply reservoir for the towns of Ansonia and Derby.

h. Design and Construction History - Very little is known of the original design and construction of the project. The Main Dam appears today as it is shown on an undated, anonymous drawing entitled "Plan of Overflow Dam at Storage Reservoir of Birmingham Water Co." (Sheet B-2). As described in Section 1.2.b, the drawing depicts a raising of the dam. The storage of the reservoir is shown on an 1887 drawing by H.S. Whipple, Civil and Sanitary Engineer; however, it is not known if this date coincides with any construction at the site.

i. Normal Operational Procedures - Normally, the gate to the water supply main is kept open. This line can be controlled farther downstream to either feed into the Lower Reservoir or to bypass it and feed directly to a chlorination station below the Lower Reservoir.

### 1.3 PERTINENT DATA

a. Drainage Area - The drainage area is 0.43 square miles of sparsely to heavily developed rolling to mountainous terrain.

b. Discharge at Damsite - Discharge is over the spillway, through the 12 inch supply pipe, and through the 12 inch low-level outlet.

#### 1. Outlet Works (Conduits)

12 inch low-level outlet  
@ invert el. 290.0+:

19+ cfs (reservoir  
level to top of dam)

2. Maximum flood at damsite:	N/A (water released through low-level outlet if reservoir level rises above spillway crest)
3. Ungated spillway capacity @ top of dike el. 309.5:	240 cfs
top of dam el. 309.7:	270 cfs
4. Ungated spillway capacity @ test flood el. 310.1:	340 cfs
5. Gated spillway capacity @ normal pool:	N/A
6. Gated spillway capacity @ test flood:	N/A
7. Total spillway capacity @ test flood el. 310.1:	340 cfs
8. Total project discharge @ top of dike el. 309.5:	259+ cfs
9. Total project discharge @ test flood el. 310.1:	870 cfs

c. Elevations - Elevations are on National Geodetic Vertical Datum (NGVD), based on an assumed spillway crest elevation of 307.0, which corresponds to the reservoir water surface elevation shown on USGS Ansonia Quadrangle Map, 1972.

1. Streambed at toe of Main Dam:	289.2+
Ground surface at toe of East Dam:	294.0+
Ground surface at toe of Dike:	302.5+
2. Bottom of cutoff:	289.0+ (Main Dam - others not known)
3. Maximum tailwater:	Not known
4. Normal pool:	307.0+
5. Full flood control pool:	N/A
6. Spillway crest (ungated):	307.0 (Assumed datum)
7. Design surcharge (original design):	Not known
8. Top of Main Dam:	309.7+
Top of East Dam:	310.0+
Top of dike:	309.5+
9. Test flood surcharge:	310.1

d. Reservoir Length

- |                         |            |
|-------------------------|------------|
| 1. Normal pool:         | 3,100+ ft. |
| 2. Flood control pool:  | N/A        |
| 3. Spillway crest pool: | 3,100+ ft. |
| 4. Top of dam pool:     | 3,200+ ft. |
| 5. Test flood pool:     | 3,200+ ft. |

e. Reservoir Storage

- |                         |               |
|-------------------------|---------------|
| 1. Normal pool:         | 196+ acre-ft. |
| 2. Flood control pool:  | N/A           |
| 3. Spillway crest pool: | 196+ acre-ft. |
| 4. Top of dam pool:     | 310+ acre-ft. |
| 5. Test flood pool:     | 330+ acre-ft. |

f. Reservoir Surface

- |                         |             |
|-------------------------|-------------|
| 1. Normal pool:         | 34+ acres   |
| 2. Flood control pool:  | N/A         |
| 3. Spillway crest pool: | 34+ acres   |
| 4. Top of dam pool:     | 37.1+ acres |
| 5. Test flood pool:     | 37.7+ acres |

g. Dam

- |               |  |
|---------------|--|
| 1. Type:      | Masonry gravity structures with upstream and/or downstream embankments |
| 2. Length     |  |
| Main Dam:     | 345 ft.  |
| East Dam:     | 423 ft.  |
| Dike:         | 200 ft.  |
| 3. Height     |  |
| Main Dam:     | 20.8 ft.   |
| East Dam:     | 16.2 ft.   |
| Dike:         | 7.0 ft.  |
| 4. Top width: | 3-4.8 ft. (both dams)<br>25 ft. (dike)                                 |

- |   |   |
|---|---|
| 5. Side slopes                            |   |
| Main Dam:                                 | upstream batter -<br>1H to 4V<br>downstream batter -<br>1H to 9V (tiered)       |
| East Dam:                                 | upstream batter -<br>vertical<br>downstream slope -<br>2H to 1V                 |
| Dike:                                     | upstream batter -<br>vertical<br>downstream slope<br>4H to 1V                   |
| 6. Zoning:                                | Earth embankments on<br>upstream and/or down-<br>stream side of masonry<br>wall |
| 7. Impervious core:                       | Masonry walls   |
| 8. Cutoff:                                | Founded on rock,<br>except for right end<br>of Main Dam                         |
| 9. Grout curtain:                         | N/A   |
| 10. Other:                                | N/A   |
| h. <u>Diversion and Regulating Tunnel</u> | N/A   |
| i. <u>Spillway</u>                        |   |
| 1. Type:                                  | Broad-crested masonry<br>weir of trapezoidal<br>cross-section                   |
| 2. Length of weir:                        | 20.5 ft.  |
| 3. Crest elevation:                       | 307.0 (Assumed datum)   |
| 4. Gates:                                 | N/A   |
| 5. Upstream channel:                      | None  |
| 6. Downstream channel:                    | Riprap splash apron<br>to channel lined with<br>dry-laid masonry walls.         |
| 7. General:                               | Concrete cap and<br>stanchions for stop<br>planks                               |

j. Regulating Outlets

Low-level outlet

- |                       |                    |
|-----------------------|--------------------|
| 1. Invert:            | 290.0 <sub>+</sub> |
| 2. Size:              | 12 inch diameter   |
| 3. Description:       | Cast iron          |
| 4. Control mechanism: | Manual             |
| 5. Other:             | N/A                |

Supply Pipe

- |                       |                  |
|-----------------------|------------------|
| 1. Invert:            | Not known        |
| 2. Size:              | 12 inch diameter |
| 3. Description:       | Cast iron        |
| 4. Control mechanism: | Manual           |
| 5. Other:             | N/A              |

## SECTION 2: ENGINEERING DATA

### 2.1 DESIGN DATA

The available data consists of inventory data by the State of Connecticut, correspondence concerning placement of flashboards at the dam in 1942, and drawings of the project by the Birmingham Water Company. The drawings consist of an 1887 drawing by H.S. Whipple, Civil and Sanitary Engineer showing the reservoir storage and two undated, anonymous drawings entitled "Plan of Overflow Dam at Storage Reservoir of Birmingham Water Company" and "Plan of Masonry in Addition to that of Main Dam of Birmingham Water Co's. Storage Reservoir" (See Appendix B).

The drawings and correspondence indicate the design features stated previously in this report.

2.2 CONSTRUCTION DATA - No information is available.

### 2.3 OPERATIONS

Reservoir level readings are taken daily at the dam. No formal operations records are known to exist.

### 2.4 EVALUATION OF DATA

a. Availability - Available data was provided by the State of Connecticut and the owner. The owner made the project available for visual inspection.

b. Adequacy - The limited amount of detailed engineering data available was inadequate to perform an in-depth assessment of the dam, therefore, the final assessment of this dam must be based primarily on visual inspection, performance history, hydraulic computations of spillway capacity and hydrologic estimates

c. Validity - A comparison of record data and visual observations reveals no significant discrepancies in the record data.

### SECTION 3: VISUAL INSPECTION

#### 3.1 FINDINGS

a. General - The project is in fair condition. The inspection revealed several areas requiring maintenance and monitoring. At the time of inspection, the reservoir level was 1.1 feet below the spillway crest at elevation 305.9.

#### b. Dam

##### Main Dam

Top of Dam - The top of the dam consists of the top of the masonry wall and is in good condition (Photos 1 & 3). Minor cracking and spalling of the mortar joints was noted.

Upstream Face - The masonry upstream face of the dam is in good condition. The stone blocks are in good condition, exhibiting almost no weathering. The mortar joints, which were repointed in 1969, are in fair condition with minor cracking and spalling noted. Weedy vegetation is growing from cracks in the mortar on the upstream face and top of the wall. For a length of approximately 140 feet at the left end of the Main dam, up to 1.5 feet of concrete has been added to the upstream face, including the upstream face of the spillway (Photo 1). This concrete is in good condition, except for some cracking and loss of material at the right end of the spillway.

Downstream Face - The downstream face of the Main Dam is in fair condition. Seepage was noted exiting from several locations on the downstream face below elevation 300, or approximately 6 feet below the upstream water level. All seepage was clear and no major individual seeps were observed. The quantity of seepage could not be measured, but is estimated to total less than 10 gallons per minute (gpm). The masonry is in fair condition with some cracking and spalling of the mortar joints and a later mortar resurfacing. Weedy vegetation is growing from cracks in the mortar, especially in the tiered area where there is wetness due to seepage (Photo 2). There is extremely dense brush growth at the toe of the dam, making inspection of some areas on the downstream face impossible. The 116 foot long section at the right end of the dam includes an earth embankment on the downstream side of the masonry wall. Extremely dense brush covers this entire embankment (Photo 3).

Spillway - The spillway is in good condition. Cracking of the concrete cap and sidewall was noted at the right end of the spillway. A little grass is growing from joints in the concrete and there is minor spalling of the spillway crest (Photo 7).

##### Dike to Left of Main Dam

Top of Dike - The top of the dike embankment is level with the top of the masonry wall and is in good condition, with thick grass cover (Photo 4).



Upstream Face - The masonry wall on the upstream side of the embankment is in good condition. It appears to be founded on bedrock. At the left end, the ground surface extends upstream from the wall and brush growth is present in this area (Photo 4).

Downstream Slope - Due to the presence of numerous large trees and brush, the downstream slope is in poor condition. However, no seepage, sloughing or erosion was observed.

#### East Dam

Top of Dam - The top of the embankment on the downstream side of the masonry wall is 3 feet lower than the top of the wall and is covered with low vegetation and some brush. Also, there is a row of pine trees along the downstream edge of the top of the embankment.

Upstream Face - The masonry of the upstream face of the East Dam is similar in appearance to that of the Main Dam and is in good condition (Photo 5).

Downstream Slope - Low vegetation, such as ferns, and some brush is present on the downstream slope. There are several trees growing in a wet, swampy area at the toe. Seepage was observed to be emanating along the toe of the slope, where the toe is at or below elevation 300, or approximately 6 feet below the upstream water level. All seepage was clear and no major individual seeps were noted. The quantity of seepage could not be measured, but is estimated to total less than 6 gpm (Photo 6). All seepage is through the left section of the dam which is 16.2 feet in height and separated from the 11 foot high right section by a natural rock ridge which has a top elevation approximately 5 feet below the top of the dam.

c. Appurtenant Structures - The masonry intake structure is in poor condition (Photo 8). The mortar joints of the structure are extensively cracked and/or leached. The wood service bridge from the dam has partially collapsed, making access to the intake structure unsafe. Reportedly, 12 inch gate valves which control the low-level outlet and supply line are operable. Due to the unsafe condition of the service bridge, the gate valve stems and stands could not be inspected.

d. Reservoir Area - The area surrounding the reservoir is wooded and undeveloped, except for a 400 foot long section along the west shoreline, where Prindle Avenue is located.

e. Downstream Channel - The downstream channel to the Lower Reservoir is approximately 4 feet high by 4 feet wide and lined with dry-laid masonry.

### 3.2 EVALUATION

Based upon the visual inspection, the project is in fair condition. The manner in which the features identified in Section 3.1 could affect the future condition and/or stability of the project is as follows:

1. Trees and brush on the dam embankments and at the toe of the masonry dam could be uprooted, causing damage to the structures. Penetration of root systems could cause displacement of masonry blocks and/or provide seepage paths through the dams.
2. Continued deterioration of the masonry intake structure could threaten its stability.
3. The service bridge to the intake structure could collapse, making access to the structure from the dam impossible.
4. Seepage through the dams could cause leaching of mortar joints of the masonry walls or internal erosion of the earth embankments.
5. Continued cracking of the mortar joints could weaken the masonry portions of the project.

## SECTION 4: OPERATIONAL AND MAINTENANCE PROCEDURES

### 4.1 OPERATIONAL PROCEDURES

a. General - From the dam, water is normally released via the 12 inch supply pipe, which is controlled to either feed the Lower Reservoir or bypass it and feed directly to a chlorination station downstream of the Lower Dam. Reservoir level readings are taken daily. If the reservoir level rises above the spillway crest, the low-level outlet is opened in order to maintain as much freeboard as possible.

b. Description of Any Warning System in Effect - The owner maintains surveillance of the dam during unusually high precipitation and/or reservoir levels. Should a problem arise at the dam, the owner would contact the local Civil Defense.

### 4.2 MAINTENANCE PROCEDURES

a. General - The masonry portions of the project were repointed in 1969 and are maintained on an as-needed basis. No maintenance is performed to the embankment portions of the project.

b. Operating Facilities - The operating facilities are exercised and lubricated on a regular basis.

### 4.3 EVALUATION

The operational and maintenance procedures are fair. A formal program of operational and maintenance procedures should be implemented, including documentation to provide records for future reference. Remedial operational and maintenance procedures are presented in Section 7.3.

## SECTION 5: EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

### 5.1 GENERAL

The Upper Ansonia Reservoir Dam watershed is 0.43 square miles of rolling to mountainous wooded terrain. The dam impoundment is presently used for public water supply purposes.

The reservoir is impounded by a masonry and earth dam, a masonry and earth dike, and a masonry dam which includes a spillway section. It is basically a high surcharge storage - low spillage type project. The available storage reduces the outflow from a Probable Maximum Flood (PMF) of 1200 cubic feet per second (cfs) to 870 cfs and the  $\frac{1}{2}$  PMF outflow from 600 cfs to 310 cfs.

### 5.2 DESIGN DATA

No computations were available for the original design of the dam.

### 5.3 EXPERIENCE DATA

Although daily lake level readings have been taken since the Ansonia-Derby Water Company acquired the dam, they do not necessarily reflect peak flows because the Water Company opens the low-level outlet when water begins to flow over the spillway crest. During heavy precipitation experienced in January 1979, the reservoir level rose from a low of  $26\frac{1}{2}$  inches below the spillway crest on Jan. 1 to a high of  $1\frac{1}{2}$  inches above the spillway crest on Jan. 25.

### 5.4 VISUAL OBSERVATIONS

The top of the dam has an elevation of 309.7. The dike to the left of the dam has a top elevation that varies from 309.5 near the dam to 310 at the other end. The East Dam has a top elevation of 310. At test flood, a road depression at Prindle Avenue (See Sheet B-1) allows a flow of approximately 30 cfs to divert from the watershed above elevation 310.

### 5.5 TEST FLOOD ANALYSIS

Based upon the U.S. Army Corps of Engineers "Preliminary Guidance for Estimating Maximum Probable Discharges" dated March, 1978; the watershed classification (Rolling to Mountainous) and the watershed area of 0.43 square miles, a PMF of 1200 cfs or 2800 cfs per square mile is estimated at the damsite. In accordance with the size (small) and hazard (high) classification, the range of test floods to be considered is from the  $\frac{1}{2}$  PMF to the PMF. Based on the degree of hazard associated with a breach of the dam, the test flood for Upper Ansonia Reservoir Dam is equivalent to the PMF. The pond level at the start of the test flood is considered to be at spillway crest elevation 307. The peak outflow for the test flood is estimated at 870 cfs and this flow will overtop the low point of the dike by 0.6 feet. Based on hydraulics computations, the spillway capacity to the first point of overflow of the project is 240 cfs, which is equivalent to 28% of the routed test flood outflow (Appendix D-6).

## 5.6 DAM FAILURE ANALYSIS

The dam failure analysis is based on the April, 1978 Army Corps of Engineers "Rule of Thumb Guidance for Estimating Downstream Dam Failure Hydrographs". Since a breach of any part of the project would affect the same downstream areas, the most critical condition, a breach of the East Dam, is analyzed. With the pond level at the top of the dike, peak outflow before failure of the East Dam would be about 240 cfs and the peak failure outflow from the dam breaching would total about 8,600 cfs. This sudden outflow would cause the Lower Ansonia Reservoir Dam to be overtopped by 2.8 feet and cause a rise in the water level of the stream at the initial impact area from a depth of 0.9 feet just before the breach to a depth of about 5.9 feet shortly after the breach. This rapid, 5.0 foot increase in water level will inundate numerous houses by up to 5 feet, possibly causing the loss of more than a few lives as well as substantial economic loss (Appendix D-14). Based on the dam failure analysis, Upper Ansonia Reservoir Dam is classified as a high hazard dam.

## SECTION 6: EVALUATION OF STRUCTURAL STABILITY

### 6.1 VISUAL OBSERVATIONS

The visual inspection did not reveal any indications of stability problems. The project consists of 3 masonry gravity structures and is founded on a dense gray schist bedrock for the majority of its length. The right end of the Main dam does not appear to be founded on bedrock, but the actual foundation conditions could not be observed. Items described in section 3, such as trees and brush on the embankments, deterioration of the masonry intake structure and service bridge, and seepage through the dams are not stability concerns at the present time.

### 6.2 DESIGN AND CONSTRUCTION DATA

Drawings of the project depict cross-sections of the masonry portions of the Main Dam, the East Dam, and the dike to the left of the Main Dam. Where the Main Dam is approximately 20 feet high, the masonry has a top width of 4.5 feet and a base width of approximately 24 feet. In addition, the drawings show an earth embankment with an approximate top elevation of 305 on the upstream side of the masonry dam. The drawings confirm that most of the Main Dam is founded on bedrock, but show it keyed into rock only for a length of approximately 48 feet. Where the East Dam reaches its maximum height of 16 feet, the upstream masonry wall is shown to be 4.8 feet wide at its top and 6 feet wide at its base. The upstream masonry wall of the dike is shown to be 3 feet wide at the top and base. These drawings also show the volume of masonry used.

### 6.3 POST-CONSTRUCTION CHANGES

At some unknown date, the original dam was raised 5 feet to its present height. At some later date, the masonry was repointed and concrete was added to a portion of the upstream face of the Main Dam. These post-construction changes do not appear to impair the structural stability of the project.

### 6.4 SEISMIC STABILITY

The project is in Seismic Zone 1, and according to recommended guidelines, need not be evaluated for seismic stability.

## SECTION 7: ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

### 7.1 PROJECT ASSESSMENT

a. Condition - Based upon the visual inspection at the site and past performance, the project is in fair condition. No evidence of instability was observed in the masonry walls, spillway, or embankments; however, there are several items which require maintenance, repair and monitoring.

Based upon the U.S. Army Corps of Engineers' "Preliminary Guidance for Estimating Maximum Probable Discharges" dated March, 1978, the watershed area and classification, and hydraulic/hydrologic computations, peak inflow to the reservoir at test flood is 1200 cfs; peak outflow is 870 cfs, with the project overtopped by 0.6 feet. Based upon hydraulics computations, the spillway capacity to the top of the project is 240 cfs, which is equivalent to 28% of the routed test flood outflow.

b. Adequacy of Information - The information available is such that an assessment of the condition and stability of the project must be based on visual inspection, past performance and sound engineering judgement.

c. Urgency - It is recommended that the measures presented in Section 7.2 and 7.3 be implemented within one year of the owner's receipt of this report.

### 7.2 RECOMMENDATIONS

It is recommended that further studies be made by a registered professional engineer qualified in dam design and inspection pertaining to the following items. Recommendations made by the engineer should be implemented by the owner.

1. Removal of all trees and brush from the project and from within 10 feet of the toe of the dam. This should include proper backfilling of root cavities with selected soils.
2. Investigation of the origin and significance of seepage through the Main Dam and the East Dam and establishment of a seepage monitoring program.
3. A more detailed hydraulic/hydrologic analysis, including an assessment of the ability of the masonry structures to withstand overtopping.

### 7.3 REMEDIAL MEASURES

a. Operation and Maintenance Procedures - The following measures should be undertaken by the owner within the length of time indicated in section 7.1.c, and continued on a regular basis:

1. Round-the-clock surveillance should be provided during periods of heavy precipitation or high project discharges. A formal downstream warning system should be developed, to be used in case of emergencies at the dam.
2. A formal program of operation and maintenance procedures should be instituted and fully documented to provide accurate records for future reference.
3. A comprehensive program of inspection by a registered professional engineer qualified in dam inspection should be instituted on an annual basis.
4. After removal of trees and brush, grassy vegetation should be established on the embankments.
5. The cracked or leached mortar joints of the masonry intake structure and the other masonry portions of the project should be repaired.
6. The service bridge to the intake structure should be replaced.

#### 7.4 ALTERNATIVES

This study has identified no practical alternatives to the above recommendations.



**APPENDIX A**  
**INSPECTION CHECKLIST**

VISUAL INSPECTION CHECK LIST  
PARTY ORGANIZATION

PROJECT Upper Ansonia  
Reservoir Dam

DATE: Aug. 8, 1980

TIME: 10:00 am

WEATHER: Hazy, humid, 80°

W.S. ELEV. 305.9 U.S. Dry DN. S

<u>PARTY:</u>	<u>INITIALS:</u>	<u>DISCIPLINE:</u>
1. <u>Peter Heynen</u>	<u>PH</u>	<u>Geotechnical</u>
2. <u>Theodore Stevens</u>	<u>TS</u>	<u>Geotechnical</u>
3. <u>Hector Moreno</u>	<u>HM</u>	<u>Hydraulics</u>
4. <u>Robert Jahn</u>	<u>RJ</u>	<u>Hydraulics</u>
5. _____	_____	_____
6. _____	_____	_____

<u>PROJECT FEATURE</u>	<u>INSPECTED BY</u>	<u>REMARKS</u>
1. <u>Main Dam</u>	<u>PH, TS, HM, RJ</u>	
2. <u>East Dam</u>	<u>PH, TS, HM, RJ</u>	
3. <u>Dike</u>	<u>PH, TS, HM, RJ</u>	
4. <u>Intake Structure</u>	<u>PH, TS, HM, RJ</u>	
5. <u>Spillway</u>	<u>PH, TS, HM, RJ</u>	
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		
11. _____		
12. _____		

## PERIODIC INSPECTION CHECK LIST

Page A-2PROJECT Upper Ansonia Res. Dam DATE 8-8-80PROJECT FEATURE Main Dam BY PH, TS, HM, RS

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	309.7
Current Pool Elevation	305.9
Maximum Impoundment to Date	307.1 ± (known)
Surface Cracks	Minor cracking of mortar
Pavement Condition	N/A
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	Appears good
Horizontal Alignment	Appears good
Condition at Abutment and at Concrete Structures	Good
Indications of Movement of Structural Items on Slopes	N/A
Trespassing on Slopes	N/A
Sloughing or Erosion of Slopes or Abutments	None observed
Rock Slope Protection-Riprap Failures	N/A
Unusual Movement or Cracking at or Near Toes	None observed
Unusual Embankment or Downstream Seepage	Minor seepage ± 10 gpm tot.
Piping or Boils	None observed
Foundation Drainage Features	N/A
Toe Drains	N/A
Instrumentation System	N/A

## PERIODIC INSPECTION CHECK LIST

Page A-3PROJECT Upper Ansonia Res. Dam DATE 8-8-80PROJECT FEATURE East Dam BY PH, JS, HM, RJ

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	310.0
Current Pool Elevation	305.9
Maximum Impoundment to Date	307.1 ± (known)
Surface Cracks	Minor cracking of mortar
Pavement Condition	N/A
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	Appears good
Horizontal Alignment	Appears good
Condition at Abutment and at Concrete Structures	Good
Indications of Movement of Structural Items on Slopes	N/A
Trespassing on Slopes	None observed
Sloughing or Erosion of Slopes or Abutments	None observed
Rock Slope Protection-Riprap Failures	N/A
Unusual Movement or Cracking at or Near Toes	None observed
Unusual Embankment or Downstream Seepage	Minor (±6 gpm total)
Piping or Boils	None observed
Foundation Drainage Features	N/A
Toe Drains	N/A
Instrumentation System	N/A

## PERIODIC INSPECTION CHECK LIST

Page A-4PROJECT Upper Ansonia Res. Dam DATE 8-8-80PROJECT FEATURE Dike BY PH, TS, RJ, HM

AREA EVALUATED	CONDITION
<u>DIKE EMBANKMENT</u>	
Crest Elevation	309.5
Current Pool Elevation	305.9
Maximum Impoundment to Date	307.1± (known)
Surface Cracks	Minor cracks in mortar
Pavement Condition	N/A
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	Appears good
Horizontal Alignment	Top el varies 309.5-310.0
Condition at Abutment and at Concrete Structures	Good
Indications of Movement of Structural Items on Slopes	N/A
Sloughing or Erosion of Slopes or Abutments	None observed
Rock Slope Protection-Riprap Failures	None observed
Unusual Movement or Cracking at or Near Toes	None observed
Unusual Embankment or Downstream Seepage	None observed
Piping or Boils	None observed
Foundation Drainage Features	N/A
Toe Drains	N/A
Instrumentation System	N/A
Trespassing on Slopes	None observed

## PERIODIC INSPECTION CHECK LIST

Page A-5PROJECT Upper Ansonia Res. DamDATE 8-8-80PROJECT FEATURE Intake StructureBY PH, TS, HM, RJ

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS-INTAKE CHANNEL AND</u> <u>INTAKE STRUCTURE</u></p> <p>a) <u>Approach Channel</u></p> <p>Slope Conditions</p> <p>Bottom Conditions</p> <p>Rock Slides or Falls</p> <p>Log Boom</p> <p>Debris</p> <p>Condition of Concrete Lining</p> <p>Drains or Weep Holes</p> <p>b) <u>Intake Structure</u></p> <p>Condition of <sup>Masonry</sup><del>Concrete</del></p> <p>Stop Logs and Slots</p>	<p>Could not observe approach channel - intake structure located in reservoir <math>\pm 15'</math> from upstream edge of dam.</p> <p>Wood service bridge to structure partially collapsed, making access unsafe.</p> <p>Poor - much cracking and leaching of mortar joints</p> <p>Could not observe</p>

A-5


## PERIODIC INSPECTION CHECK LIST



Page A-6PROJECT Upper Ansonia Res. DamDATE 8-8-80PROJECT FEATURE SpillwayBY FH, TS, HM, RS

AREA EVALUATED	CONDITION
<u>OUTLET WORKS-SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a) <u>Approach Channel</u>  General Condition  Loose Rock Overhanging Channel  Trees Overhanging Channel  Floor of Approach Channel	Appears good None observed None observed Could not observe
b) <u>Weir and Training Walls</u>  General Condition of Concrete  Rust or Staining  Spalling  Any Visible Reinforcing  Any Seepage or Efflorescence  Drain Holes	Good None observed Minor cracking-right end No Minor seepage from D/S face N/A
c) <u>Discharge Channel</u>  General Condition  Loose Rock Overhanging Channel  Trees Overhanging Channel  Floor of Channel  Other Obstructions	Fair Dry-laid walls-fallen rocks in places Yes-channel thru wooded area Gravel, cobbles None observed


**APPENDIX B**  
**ENGINEERING DATA AND CORRESPONDENCE**








SECTION AT 'A'



SECTION AT 'B'



SECTION AT 'C'




SECTION AT 'D'

### SECTIONS


### NOTES

1. THIS SH  
DRAWING  
RESERVE  
1" = 10'

2. NO ELE  
WATER  
ON THE  
THE NO  
ALL OT  
SPILLWAY



**PLAN**






**PROFILE**

**NOTES :**

1. THIS SHEET WAS COMPILED FROM AN ANONYMOUS, UNDATED DRAWING ENTITLED " PLAN OF OVERFLOW DAM AT STORAGE RESERVOIR OF BIRMINGHAM WATER CO. " SCALE: HORIZONTAL 1" = 10', VERTICAL 1" = 8'.

2. NO ELEVATIONS WERE AVAILABLE FOR THE DAM, THEREFORE THE WATER SURFACE ELEVATION OF 307.0 FOR THE RESERVOIR SHOWN ON THE U.S.G.S. ANSONIA QUADRANGLE MAP WAS ASSUMED TO BE THE M.S.V.D. ELEVATION OF THE SPILLWAY CREST. ALL OTHER ELEVATIONS SHOWN ARE REFERENCED TO THE ASSUMED SPILLWAY CREST ELEVATION.

CAHN ENGINEERS INC WALLINGFORD CONNECTICUT ENGINEER		U.S. ARMY ENGINEER DISTRICT NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS			
MAIN DAM - PLAN, PROFILE & SECTIONS			
<b>UPPER ANSONIA RESERVOIR DAM</b>			
TR - NAUGATUCK RIVER		DEPT. CONNECTICUT	
OWN. BY	CKD. BY	APP. BY	SCALE: H: 1" = 20', V: 1" = 16'
R.F.	HSS	Pm	DATE: SEPT '980 SHEET B-2





#### NOTES :


1. THIS SHEET WAS COMPILED FROM AN ANONYMOUS, UNDATED DRAWING ENTITLED " PLAN OF MASONRY IN ADDITION TO THAT OF MAIN DAM OF BIRMINGHAM WATER COS. STORAGE RESERVOIR " SCALE : 1" = 10'

2. NO ELEVATIONS WERE AVAILABLE FOR THE DAM. THEREFORE THE WATER SURFACE ELEVATION OF 307.0 FOR THE RESERVOIR SHOWN ON THE U.S.G.S. ANSONIA QUADRANGLE MAP WAS ASSUMED TO BE THE M.G.V.D. ELEVATION OF THE SPILLWAY CREST. ALL OTHER ELEVATIONS SHOWN ARE REFERENCED TO THE ASSUMED SPILLWAY CREST ELEVATION

Total Length 423 Contents 23,556 cu ft



ft. Contents 3701 cu ft.



LOW POINT OF TOP OF DIKE  
EL. 309.5

CAMM ENGINEERS, INC. WALLINGFORD, CONNECTICUT ENGINEER		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS			
EAST DAM B DIKE—PROFILES			
UPPER ANSONIA RESERVOIR DAM			
DRAWN BY: TSS		CHECKED BY: HMA	
DATE: SEPT 1980		SHEET B-3	

UPPER ANSONIA RESERVOIR DAM

EXISTING PLANS

"Capacity of Upper Reservoir - Derby Hill"  
Birmingham Water Company  
H.S. Whipple, Civil and Sanitary Engineer  
Feb. 26, 1887

"Plan of Overflow Dam at Storage Reservoir of Birmingham  
Water Co."  
anonymous  
undated

"Plan of Masonry in addition to that of Main Dam of  
Birmingham Water Co's. Storage Reservoir  
anonymous  
undated

# SUMMARY OF DATA AND CORRESPONDENCE

<u>DATE</u>	<u>TO</u>	<u>FROM</u>	<u>SUBJECT</u>	<u>PAGE</u>
July 17, 1942	Birmingham Water Company Derby, Conn.	V.B. Clarke, Engineer State Board for the Supervision of Dams	Permission to install flashboards	B-3
-	File	State Board for the Supervision of Dams	Inventory Data	B-4

July 17, 1942

V. B. Carke

The Birmingham Water Company  
Derby, Conn.

Dear Sirs:

Through your Engineer, Mr. Clarence M. Blair a request has been made for permission to install flash-boards on the #1 and #2 Dams at Derby Hill.

I have investigated this matter and permission is hereby granted for you to install these flash-boards not over 10 inches in height.

I believe you should make some provision so that if any appreciable amount of water flows over these flash boards they can be removed in sections so that there will not be over 10 inches of water over the masonry spillway.

Very truly yours,

Engineer, for  
State Board of Supervision of Dams

VBC:M

Copies to: C.M. Blair, Engineer  
General Sanford B. Wadhams, Chairman



7  
CT 29

STATE BOARD FOR THE SUPERVISION OF DAMS  
INVENTORY DATA

NAME OF DAM OR POND Ansonia Res

CODE NO. 14

LOCATION OF STRUCTURE:

Town Derby

Name of Stream Tributary to Naugatuck

U.S.G.S. Quad. Ansonia Long. 73-10-7 Lat. 41-11-3

OWNER: Ansonia  
Derby Water Company

Address Derby

Telephone \_\_\_\_\_

Pond Used For: Reservoir DA 0.155M

Dimensions of Pond: Width \_\_\_\_\_ Length \_\_\_\_\_ Area 31.3

Depth of Water below Spillway Level (Downstream) 7

Total Length of Dam \_\_\_\_\_ Length of Spillway \_\_\_\_\_

Height of Abutments above Spillway 3

Type of Spillway Construction \_\_\_\_\_


Type of Dike Construction \_\_\_\_\_

Downstream Conditions \_\_\_\_\_

Summary of File Data \_\_\_\_\_

Remarks This pond was formed by construction of two dikes and a dam. It is a structure of major importance and Board Member should inspect it or at least obtain information from Water Company.

**APPENDIX C**  
**DETAIL PHOTOGRAPHS**



NOTE: PHOTOS 5 & 6 ARE OF THE EAST DAM  
8 ARE NOT SHOWN ON THIS PLAN.

PHOTO LOCATION PLAN

UPPER ANSONIA RES. DAM

SHEET C-1



Photo 1 - Upstream face and top of Main Dam (8/8/80).



Photo 2 - Seepage and vegetation on downstream face of Main Dam (8/8/80).

US ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS.

CAHN ENGINEERS, INC.  
WALLINGFORD, CONN.  
ENGINEER

NATIONAL PROGRAM OF  
INSPECTION OF  
NON-FED. DAMS

Upper Ansonia River  
Tr. Naugatuck River  
Derby, Connecticut  
CEB 20-7-80  
DATE Sept. '80 PAGE 1



Photo 3 - Right end of Main Dam, 5 to 6 ft. dense vegetation on crest of dam on downstream side of wall (8/8/80).



Photo 4 - Dike to left of Main Dam (8/8/80).

US ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS.

CAHN ENGINEERS, INC.  
WALTHAM, MASS.  
ENGINEER

NATIONAL PROGRAM OF  
INSPECTION OF  
NON-FED. DAMS

Upper Ansonia Res. on  
Tr-Naugatuck River  
Derby, Connecticut  
CE # 27-735-E  
DATE Sept. 1980 PAGE 1




Photo 5 - Upstream face of left section of East Dam  
( 8/8/80).



Photo 6 - Seepage at toe of left section of East Dam  
(8/8/80).

US ARMY ENGINEER DIV NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS

CAHN ENGINEERS INC  
WALLINGFORD, CONN  
ENGINEER

NATIONAL PROGRAM OF  
INSPECTION OF  
NON-FED. DAMS

Upper Ansonia Res. Dam  
Tr-Naugatuck River  
Derby, Connecticut  
CE # 27 785 KC  
DATE Sept. '80 PAGE 6-5



Photo 7 - Spillway crest (8/8/80).




Photo 8 - Intake structure and service bridge (8/8/80).

US ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS

CAHN ENGINEERS, INC.  
WALLINGFORD, CONN.  
ENGINEER


NATIONAL PROGRAM OF  
INSPECTION OF  
NON-FED. DAMS

Upper Ansonia Res. Dam  
Tr-Naugatuck River  
Derby, Connecticut  
CE# 27 785 KC  
DATE Sept. '80 PAGE C-4

1

**APPENDIX D**  
**HYDRAULICS/HYDROLOGIC COMPUTATIONS**





Project INSPECTION OF NON-FEDERAL DAMS IN NEW ENGLAND Sheet D-1 of 14  
Computed By HLL Checked By CAR Date 7/15/80  
Field Book Ref. \_\_\_\_\_ Other Refs. CE #27-785-HA Revisions \_\_\_\_\_

### HYDROLOGIC/HYDRAULIC INSPECTION

#### UPPER ANSONIA (DERBY) RESERVOIR, DERBY, CT.

#### 1) PERFORMANCE AT PEAK FLOOD CONDITIONS

##### 1) PROBABLE MAXIMUM FLOOD (PMF)

a) WATERSHED CLASSIFIED AS "ROLLING" TO "MOUNTAINOUS"

b) WATERSHED AREA: D.A. =  $0.43^{SQ MI}$

NOTE: D.A. FROM CONN. D.E.P. BULLETIN NO. 1, 1972 (GAZETTEER OF NATURAL DRAINAGE AREAS), p. 66

##### c) PEAK FLOODS (FROM NEO-ACE GUIDELINES - GUIDE CURVES FOR PMF)

i) FROM GUIDE CURVES BY EXTRAPOLATION TO D.A.  $< 2^{SQ MI}$

$$CSM = 2800 \text{ CFS/SQ MI}$$

$$\text{ii) PMF} = 2800 \times 0.43 = \underline{1200 \text{ CFS}}$$

$$\text{iii) } \frac{1}{2} \text{ PMF} = \underline{600 \text{ CFS}}$$

#### 2) SURCHARGE AT PEAK INFLOWS (PMF AND $\frac{1}{2}$ PMF)

##### a) OUTFLOW RATING CURVE

##### (1) SPILLWAY AND OUTFLOW PROFILE FOR SURCHARGES OVERTOPPING THE DAM.

SPILLWAY (1) 20.5' LONG, BROAD CRESTED (W & S 7'), VERTICAL FACES. STONE MASONRY DAM AND DIKES AT VARIOUS LOCATIONS ALONG THE LAKE SHORE AND ALSO, OTHER TERRAIN DEPRESSIONS (ALONG PRINCIPLE AVES) WHICH ARE POTENTIAL OVERFLOW AREAS. (SEE OVERFLOW PROFILE(S) P. D. 2).

# Cahn Engineers Inc.

Consulting Engineers

Project NON-FEDERAL DAMS INSPECTION

Sheet D-2 of 14

Computed By HLH

Checked By CAR

Date 7/15/80


Field Book Ref. \_\_\_\_\_

Other Refs. CE #27-785-HA

Revisions \_\_\_\_\_

ASSUME  $C=3.0$  FOR THE SPILLWAY, DAM AND MASONRY DIKES OVERFLOW,  $C=2.8$  FOR OVERFLOW ALONG THE PAVED ROAD DEPRESSION ON PRINDLE AVE AND  $C=2.5$  AND  $C=2.0$  FOR THE ADJACENT TERRAIN OVERFLOW, DEPENDING UPON THE KIND AND THICKNESS OF THE GROUND COVER (SEE PROFILES) BELOW).

\*NOTE: W.S. ELEV. 307' MSL ON THE USGS ANSONIA, CT. QUADRANGLE SHEET (REV. 1972) IS ASSUMED TO BE SPILLWAY CREST ELEVATION ON NATIONAL GEODETIC VERTICAL DATUM (NGVD).



\*\* OTHER POSSIBLE OVERFLOWS TO PRINDLE AVE ARE ABOVE ELEV. 315 AND THEREFORE ASSUMED TO BE BEYOND MAX. FLOOD WATER LEVELS.

DATA FROM ANSONIA WATER CO. MAPS "PLAN OF OVERFLOW DAM AT STORAGE RESERVOIR AT BIRMINGHAM (MAY 1930)" AND "PLAN OF MASONRY IN ADDITION TO THAT OF MAIN DAM OF BIRMINGHAM WATER CO." AND C.E. OBSERVATIONS ON 5/20/80 BY NAME P.S.

# Cahn Engineers Inc.

## Consulting Engineers

Project NON-FEDERAL DAM: INSPECTION

Sheet D-3 of 14

Computed By HCU

Checked By CAS

Date 7/16/80

Field Book Ref. \_\_\_\_\_

Other Refs. CE #27-785-HA

Revisions \_\_\_\_\_

4) FROM INSPECTION OF THE OVERFLOW PROFILE (P.D-2) (SEE DRAWING 1-1) ABOVE THE FLOWWAY PRE-TO PASS THE DUE TO 1200' S. DIKE. THEREFORE THE OVERFLOW RATING CURVE FOR THE RANGE OF FLOWS FOR "HARVEST" CONSIDERED CAN BE APPROXIMATED AS FOLLOWS:

$$1') \text{ SECTION BC: } Q_{BC} = 0.4 \times \frac{50}{3.0} \times 2.0 (H-3)^{5/2} = \underline{5.93 (H-3)^{5/2}} ; H \leq 5.7'$$

2') SECTION CD (DIKE #1 & #2):

$$Q_{CD} = 3.0 \times 423 (H-3)^{3/2} = \underline{1270 (H-3)^{3/2}}$$

$$3') \text{ SECTION DEF: } Q_{DEF} = 0.4 \times \frac{183}{2.4} \times 2.5 (H-3)^{5/2} = \underline{76.3 (H-3)^{5/2}} ; H \leq 5.4'$$

4') SECTION FG (DIKE #3):

$$(Q_{FG})_1 = 0.4 \times 400 \times 3.0 (H-2.5)^{5/2} = \underline{480 (H-2.5)^{5/2}} ; H \leq 3.0'$$

$$(Q_{FG})_2 = 480 [(H-2.5)^{5/2} - (H-3)^{5/2}] ; H > 3.0'$$

$$5') \text{ SECTION GH: } Q_{GH} = 0.4 \times \frac{39}{4.6} \times 2.5 (H-2.5)^{5/2} = \underline{8.26 (H-2.5)^{5/2}} ; H \geq 2.1'$$

$$6') \text{ SECTION HI: } Q_{HI} = 0.4 \times \frac{30}{4.4} \times 2.5 (H-2.7)^{5/2} = \underline{6.82 (H-2.7)^{5/2}} ; H \geq 2.1'$$

7') SECTIONS IJ AND MN (MAIN DAM):

$$Q_{IJ, MN} = 3.0 \times 325 (H-2.7)^{3/2} = \underline{975 (H-2.7)^{3/2}}$$

8') FLOWWAY (SECTION KL):

$$Q_S = Q_{KL} = 3.0 \times 20.5 H^{3/2} = \underline{61.5 H^{3/2}}$$

$$9') \text{ SECTION NO: } Q_{NO} = 0.4 \times \frac{30}{4.7} \times 2.0 (H-2.7)^{5/2} = \underline{5.11 (H-2.7)^{5/2}}$$

\*NOTE FLOW OVER SLOPED SECTIONS BY APPLICATION OF FORMULA GIVEN BY THE USGS ON "MEASUREMENT OF PEAK DISCHARGE AT DAMS BY INDIRECT METHODS" BY H. HULSING (APPLICATIONS OF HYDRAULICS).

$$Q = \frac{2C_6}{5(h_3 - h_2)^{1/6}} \left[ \frac{h_3^{5/2}}{h_2^{1/2}} \right] \text{ WHERE: } Q = \text{DISCH}; C_6 = \text{DISCH. COEFF}; b = \text{SLOPE}; h_3 = h_2 = \text{SAT. TIC HEAD REFERRED TO HIGHER/LOWER ENDS OF DAM, RESPECTIVELY.}$$

# Cahn Engineers Inc.

## Consulting Engineers

Project NON FEDERAL DAM INSPECTION

Sheet D-4 of 14

Computed By HLL

Checked By GAT

Date 7/16/80

Field Book Ref. \_\_\_\_\_

Other Refs. CE #27-785-11A

Revisions \_\_\_\_\_

PRINDLE AVE. - ROAD DEPRESSION:

$$10') \text{ SECTION PQ: } Q_{PQ} = 0.4 \times 9/2.1 \times 2.5 (H-3.8)^{5/2} = 4.27 (H-3.8)^{5/2}$$

$$11') \text{ SECTION QR: } (Q_{QR})_1 = 0.4 \times 150/2.8 \times 2.8 (H-3)^{5/2} = 210 (H-3)^{5/2}; H \leq 3.8'$$

$$(Q_{QR})_2 = 210 [(H-3)^{5/2} - (H-3.8)^{5/2}]; H > 3.8'$$

$$12') \text{ SECTION RS: } Q_{RS} = 2.8 \times 150 (H-3)^{3/2} = 420 (H-3)^{3/2}$$


$$13') \text{ SECTION ST: } (Q_{ST})_1 = 0.4 \times 100/2.3 \times 2.8 (H-3)^{5/2} = 373 (H-3)^{5/2}; H \leq 3.3'$$

$$(Q_{ST})_2 = 373 [(H-3)^{5/2} - (H-3.3)^{5/2}]; H > 3.3$$

$$14') \text{ SECTION TU: } Q_{TU} = 0.4 \times 13 \times 2.5 (H-3.3)^{5/2} = 13 (H-3.3)^{5/2}$$

THE TOTAL OVERFLOW IS APPROXIMATED BY THE SUM OF ALL THE APPLICABLE FORMULAE ON ITEMS (1') THRU (14').

III) UPPER ANSONIA RESERVOIR DAM - OUTFLOW RATING CURVE



\*SEE NOTE P. D-2

# Cahn Engineers Inc.

Consulting Engineers

Project NON-FEDERAL DAMS INSPECTION

Sheet D-5 of 14

Computed By HLL

Checked By CAB

Date 7/17/80

Field Book Ref. \_\_\_\_\_

Other Refs. CE #27-785-HA

Revisions \_\_\_\_\_

## b) SURCHARGE HEIGHTS TO PASS PEAK INFLOWS ( $Q_1$ & $Q_2$ )

$$c) \text{ } Q_1 - PMF = 1200 \text{ CFS} \quad H_1 = \underline{3.5}'$$

$$d) \text{ } Q_2 = \frac{1}{2} PMF = 600 \text{ CFS} \quad H_1' = \underline{3.0}'$$

## c) EFFECT OF SURCHARGE STORAGE - PEAK OUTFLOWS

### 1) AVE. LAKE AREA ( $\bar{A}$ ) WITHIN EXPECTED SURCHARGE

1') LAKE AREA AT FLOWLINE (ELEV. 307' NGVD)\*

$A_{307} = 34.0^{AC}$

2') AREA AT CONTOUR 310' NGVD (MSC)\*

$A_{310} = 41.3^{AC}$

$\therefore$  AVE AREA WITHIN EXPECTED SURCHARGE ( $\pm$ ) 3'

$\bar{A} = 37.7^{AC}$

\*NOTE: AREAS FROM USGS ANSONIA, CT. ROAD SHEET (REV 1972) SCALE 1"=2000'. (ONLY PORTION OF RESERVOIR (BELOW ANSONIA, DERBY CO. BOUNDARY) MEASURED. THIS IS EQUAL TO THE AREA GIVEN ON ANSONIA WATER CO. DRAWING "RESERVOIR MAP" BY H.S. WHIPPLE, DATED 2/26/1887. - (SEE CURVE P. D-6)

(2) ASSUME NORMAL POOL AT FLOWLINE ELEV. 307' NGVD

(3) DETERMINE  $Q_2 = 2.43^{AC}$  (SEE P. D-1)

## (d) PEAK OUTFLOWS ( $Q_2$ & $Q_3$ )

(DETERMINED ON THE OUTFLOW RATING CURVE P. D-4, BY USING THE APPROX. ROUTING NED-ACE GUIDELINE: "SURCHARGE STORAGE ROUTING" ALTERNATE METHOD AND 19" MAX. PROBABLE R.O. IN NEW ENGLAND).

$$** \text{ } S_{B_2} = 370^{CFS} \quad H_2 = 5.14' \text{ @ } H_2 = 5.1' \text{ (ELEV. 310' NGVD)}$$

$$S_{B_3} = 310^{CFS} \quad H_3' = 2.8' \text{ (ELEV. 309.8' NGVD)}$$

\*\* (1) 30^{CFS} THROUGH ROAD DEPRESSION AT PRINCIPLE AGE (ELEV. 310' NGVD)

Project NON-FEDERAL DAMS INSPECTION

Sheet D-6 of 14

Computed By WHL

Checked By GAB

Date 7/17/80

Field Book Ref. \_\_\_\_\_

Other Ref. CE#27-785-HA

Revisions \_\_\_\_\_


### 3) SPILLWAY CAPACITY RATIO TO PEAK OUTFLOWS:

SPILLWAY CAPACITY TO:	SURCH. H (FT)	W.S. ELEV. (FT-NGVD)	SPILLWAY CAPACITY (CFS)	SPILLWAY CAPACITY AS % OF PEAK OUTFLOWS	
				Q <sub>p</sub> (870 CFS)	Q <sub>p</sub> (310 CFS)
LOW POINT**	2.5	309.5	240	28	77
TOP OF DAM	2.7	309.7	270	31	87
1/2 PMF	2.8	309.8	290	—	94
PMF	3.1	310.1	340	39	—

\* SURCHARGE ABOVE THE SPILLWAY CREST

\*\* LOW POINT AT DIKE #3 (SEE PROFILE P. D-2)

### 4) RESERVOIR AREA/STORAGE CURVES - UPPER ANSONIA RESERVOIR



© DATA FROM ANSONIA WATER CO. DUG. "RESERVOIR NO 2" BY H.G. WHIPPLE, DATED 2/26/1887

△ AREAS FROM USGS ANSONIA, CT. QUAD. SHEET (REV. 1972)

NOTE - SEE PP. D-5 (AREAS) AND D-11 (STORAGE)

Project VON FROENKE DAM INSPECTION Sheet D-7 of 14  
 Computed By WJH Checked By AB Date 7/17/80  
 Field Book Ref. \_\_\_\_\_ Other Refs. CE # 27-785-HA Revisions \_\_\_\_\_

### UPPER ANSONIA RESERVOIR DAM

### II) DOWNSTREAM FAILURE HAZARD

#### 1) POTENTIAL IMPACT AREA

UPPER ANSONIA RESERVOIR IS LOCATED (X) 500'  $\frac{1}{2}$  FROM THE LOWER RESERVOIR. BOTH DISCHARGE INTO AN UNNAMED STREAM WHICH INITIALLY RUNS PARALLEL TO HIGH ST., DERBY, FOR (X) 500'. THEN, AFTER FALLING (X) 200' ON A VERY STEEP GORGE, (X) 1200' LONG, THE STREAM IS PIPED UNDER A FULLY DEVELOPED, LOWER SECTION OF DERBY TO ITS OUTLET IN THE NAUGATUCK RIVER. ONLY ONE HOUSE WITH FIRST FLOOR ELEV. OF (X) 8.6' ABOVE THE STREAM IS LOCATED ON HIGH ST. THE LOWER SECTION OF DERBY CONTAINS, HOWEVER, NUMEROUS HOMES AND THEREFORE, IT IS CONSIDERED TO BE A POTENTIAL IMPACT AREA IN CASE OF FAILURE OF THE DAM.

#### 2) FAILURE AT UPPER ANSONIA RESERVOIR DAM.

ASSUME DISCHARGE TO TOP OF DAM ELEV. 301.7' NGVD.

FAILURE AT UPPER ANSONIA RESERVOIR DAM WOULD OCCUR AT EITHER THE MAIN DAM OR AT ONE OF THE DIKES FORMING THE RESERVOIR. HOWEVER, THE FLOOD PRODUCED BY FAILURE OF ANY OF THESE STRUCTURES WILL AFFECT ESSENTIALLY THE SAME  $\frac{1}{2}$  AREA. THEREFORE, CONDITIONS AT THE IMPACT AREAS WILL BE ANALYZED FOR THE LARGEST FLOOD FROM PRODUCED BY FAILURE OF ONE OF THESE STRUCTURES.

#### (a) FAILURE OF MAIN DAM:

(1) HEIGHT OF DAM\*  $H_0 = 20.8'$  (STREAMED ELEV. (X) 298.9' NGVD)

(2) MID-HEIGHT LENGTH\*  $L = 61'$

\*FROM ANSONIA WHITE CO. MAPS AND C.E. FIELD MEASUREMENTS ON SITE/PO BY WJH & R.J.



# Cahn Engineers Inc.

Consulting Engineers

Project NON-FEDERAL DAM INSPECTION Sheet D-8 of 14  
 Computed By HLL Checked By CAR Date 7/15/80  
 Field Book Ref. \_\_\_\_\_ Other Refs. CE # 27-785 - 1-8 Revisions 11/12/80 HLL

(ii) BREACH WIDTH (MAIN DAM) - (SEE NED ACE & DAM FAILURE GUIDELINES)

$$W_D = 0.4 \times 61 = 24.4' \quad \text{ASSUME } W_{D,D} = \underline{24.4'}$$

(iii) ASSUMED WATER DEPTH AT TIME OF FAILURE:  $Y_D = \underline{20.6'}$   
 (LOW PT. @ DIKE #3)

(iv) SPILLWAY DISCHARGE AT TIME OF FAILURE:  $Q_S = 240 \text{ cfs}$  (SEE P. D-6)

(v) BREACH OUTFLOW (SEE NED-ACE GUIDELINES)

$$Q_{D,D} = \frac{8}{27} W_D \sqrt{g} Y_D^{3/2} = 3840 \text{ cfs}$$

(vi) PEAK FAILURE OUTFLOW ( $Q_P$ ), (MAIN DAM) TO LOWER ANTONIA RESERVOIR

$$(Q_P)_D = Q_S + Q_{D,D} = 4080 \text{ cfs} \quad \text{SAY, } (Q_P)_D = \underline{4100 \text{ cfs}}$$

(vii) FLOOD DEPTH\* IMMEDIATELY R/L FROM MAIN DAM.

$$Y_D = 0.44 \times Y_D = \underline{9.1'}$$

\*(FROM RETREATING WAVE THEORY APPLIED TO DAM FAILURE)

b) FAILURE OF DIKE #1 (\*\*EAST DAM)

(i) HEIGHT OF DIKE\*\*:  $H_{DK} = 16.2'$

(ii) MID HEIGHT LENGTH\*\*:  $L_{DK} = 200'$

(iii) BREACH WIDTH - (SEE NED-ACE GUIDELINES)

$$W_{DK} = 0.4 \times 200 = 80' \quad \text{ASSUME } W_{D,D} = \underline{80'}$$

\*\* FROM ANTONIA WATER CONTROL MAPS AND C.E. FIELD MEASUREMENTS ON 5/15/80.  
 (DIKE #1 IS CALLED "EAST DAM" OR "WALL #1" ON THE ORIGINAL DRAWINGS). D-8

# Cahn Engineers Inc.

## Consulting Engineers

Project NON-FEDERAL DAMS INSPECTION

Sheet D-4 of 14

Computed By HEU

Checked By GAB

Date 7/18/80

Field Book Ref. \_\_\_\_\_

Other Refs. CE #27-785-HA

Revisions 11/12/80 HGL

(c) ASSUMED LAKE DEPTH AT TIME OF FAILURE (DIKE #1):  $Y_{DK} = 15.7'$   
(CATCH TO LOW PT. @ DIKE #3; EL. 307.5' - TOP OF DIKE (EL. 310.00'))

(d) SPILLWAY DISCHARGE AT TIME OF FAILURE:  $Q_s = 240 \text{ cfs}$  (SEE PP. D-6 & D-8)

(e) BREACH OUTFLOW (SEE NED-ACE GUIDELINES)

$$Q_{B,DK} = \frac{S}{27} W_b \sqrt{g} Y_o^{3/2} = 8370 \text{ cfs}$$

(f) PEAK FAILURE OUTFLOW  $(Q_p)_{DK}$  (DIKE #1) TO LOWER ANSONIA RESERVOIR.

$$(Q_p)_{DK} = Q_s + Q_{B,DK} = 8610 \text{ cfs} \text{ SAY, } (Q_p)_{DK} = \underline{8600 \text{ cfs}}$$

(g) FLOOD DEPTH IMMEDIATELY  $\frac{1}{2}$  FROM DIKE #1:

$$Y_{DK} = 0.44 Y_o = \underline{6.9'}$$

BECAUSE THE REMAINING DIKES ARE BOTH LOWER AND SHORTER AT MID-HEIGHT, THE PEAK OUTFLOWS RESULTING FROM THEIR FAILURE, ARE LESS CRITICAL THAN THE PEAK FLOW ESTIMATED ABOVE FOR DIKE #1.

3) ESTIMATE OF  $\frac{1}{2}$  FAILURE CONDITIONS AT POTENTIAL IMPACT AREA.

(SEE NED-ACE GUIDELINE FOR ESTIMATING  $\frac{1}{2}$  FAILURE HYDROGRAPHS)

a) PEAK FLOOD REDUCTION BY CHANNEL STORAGE IN THE CHANNEL REACH (500' TO 700' LONG) CONNECTING THE UPPER AND LOWER RESERVOIRS WILL BE NEGLECTED. THEREFORE, PEAK INFLOW TO LOWER ANSONIA RESER. WILL UPON FAILURE OF THE UPPER ANSONIA DAM (ACTUALLY THE DIKE #1) IS APPROX.  
 $(Q_p)_{LA} = \underline{8600 \text{ cfs}}$

FROM DATA ON THE ANSONIA WATER CO. DWS "PLAN AND ELEVATION OF DAM AT THE LOWER RESERVOIR OF THE BIRMINGHAM WATER CO." AND "RESERVOIR NO. 1" AND C.E. FIELD OBSERVATIONS ON 5/28/80, THE LOWER ANSONIA RESERVOIR DAM OVERFLOW

Project LOW. ANSONIA DAM & TAIL POND

Sheet D-10 of 18

Computed By WLD

Checked By GAB

Date 7/23/80


Field Book Ref. \_\_\_\_\_

Other Refs. CE 27-785-HA

Revisions 11/12/80 HLL

PROFILE AND CORRESPONDING RATING CURVE ARE APPROXIMATED AS FOLLOWS (SEE ALSO, C.E. H/H CORR. FOR LOWER ANSONIA REGION PHASE I INITIAL REPORT)

### C) OVERFLOW PROFILE




\* NOTE: W.S. ELEV. 277' MSL ON THE USGS ANSONIA, CT QUAD. SHEET (40-1472) IS ASSUMED TO BE SPILLWAY CREST ELEVATION ON NATIONAL GEODETIC VERTICAL DATUM (NGVD)

### D) RATING CURVE

THE TOTAL OVERFLOW IS APPROXIMATED BY THE FOLLOWING EQUATION AND RATING CURVE. (SEE SIMILAR DEVELOPMENT ON PP. D-3 & D-4)

$$Q = 65H^{3/2} + 638(H-2.2)^{3/2} + 557(H-2.2)^{5/2} - 327(H-2.7)^{5/2} - 117(H-2.9)^{5/2} - 655(H-3.2)^{5/2}$$



\* W.S. EL. 277.3' NGVD = (+) TOP OF DAM.

Project NON FEDERAL DAMS INSPECTION

Sheet D-11 of 14

Computed By WHE

Checked By GAB

Date 7/23/80

Field Book Ref. \_\_\_\_\_

Other Refs. CE # 27-785-11A

Revisions 11/12/80 WHE

THE CHANNEL TO FROM THE ANSONIA RESERVOIRS IS DIVIDED IN 3 REACHES (SEE P. D-7, SECT. 1). THE  $\frac{1}{2}$  REACH IS (1) 500' LONG, V-SHAPED WITH (2) 15" AND 5" TO 1" SIDE SLOPES AND AVE. REACH SLOPE OF 1.5%. THE 2<sup>ND</sup> REACH IS VERY STEEP (2) 18% SLOPE, (2) 1200' LONG AND V-SHAPED WITH (3) 3" TO 1" SIDE SLOPES. THE LOWER REACH WHERE THE STREAM IS PIPED, FORMS A VALLEY (2) 100' WIDE WITH (2) 10" TO 1" SIDE SLOPE, AND WITH AVE. REACH SLOPE OF (2) 2%. NO REDUCTION TO PEAK FLOWS, BECAUSE OF CHANNEL STORAGE, IS CONSIDERED IN THIS CHANNEL. (ASSUME  $n=0.070$  FOR ALL 3 REACHES AT FLOOD STAGE)

### b) UPPER ANSONIA RESERVOIR STORAGE AT TIME OF FAILURE:

$$S_{MAX} \approx 310^{ACFT}$$

(FROM STORAGE DATA ON THE ANSONIA WATER CO. DUG "RESERVOIR NO. 2" BY H.S. WHIPPLE, DATED FEB. 26, 1887:  $S_{W-64} \approx 196^{ACFT}$  AND C.E. SURCHARGE STORAGE TO TOP OF DAM ESTIMATE:  $S_0 \approx 113^{ACFT}$ ) - SEE CURVE P. D-6

### c) APPROXIMATE STAGE $\frac{1}{2}$ FROM DAM AFTER FAILURE:

#### c) LOWER ANSONIA RESERVOIR:

$$\text{PEAK INFLOW TO L.A.R.: } (Q_{P,14}) \approx 8600^{CFS} \text{ (SEE P. D-9)}$$

FROM C.E. AREA/SURCH STORAGE ESTIMATES OF LOWER ANSONIA RES.:

$$\text{AVE. AREA BETWEEN ELEV. 277' AND 285' NGVD: } \bar{A}_1 = 10.8^{AC}$$

$$\text{AVE. AREA BETWEEN ELEV. 280' AND 290' NGVD: } \bar{A}_2 = 15.2^{AC}$$

$$\text{SURCH STORAGE FULL, PREVIOUS TO FAILURE: } S_0 \approx 25.3^{ACFT} (S_3 = 240', H = 2.28')$$

THEREFORE, FROM APPROX. ROUTING (NEED-ACE GUIDELINES) THE OUTFLOW OF LOWER ANSONIA RESERVOIR ( $Q_{B,14}$ ) IS ESTIMATED AT:

$$(Q_B)_{14} = 7500^{CFS} \quad (H_B)_{14} \approx 5.0' \text{ (SEE RATING CURVE P. D-10)}$$

(DAM OVERTOPPED (2) 2.8' - U.S. ELEV. 282.0' NGVD)

Project NON-FEDERAL DAMS INSPECTION Sheet D-12 of 14  
 Computed By WLP Checked By EAB Date 7/23/50  
 Field Book Ref. \_\_\_\_\_ Other Refs. CE #27-785-HA Revisions 11/12/80 WLP

(i) 1<sup>ST</sup> REACH  $\frac{1}{2}$  FROM LOWER ANTONIA RESERVOIR (HIGH ST. AREA)

$$(Q_p)_1 = (Q_p)_1 = 7500 \text{ cfs} \quad (y_3)_1 = 7.9' \quad (y_c = 8.1') \quad (y_n = 11')$$

(ii) 2<sup>ND</sup> REACH  $\frac{1}{2}$  FROM L.A. RESERVOIR

$$(Q_p)_2 = (Q_p)_2 = 7500 \text{ cfs} \quad (y_3)_2 = 9.9' \quad (y_c = 13') \quad (y_n = 15')$$

(i) LOWER (3<sup>RD</sup>) REACH  $\frac{1}{2}$  FROM L.A. RESERVOIR (LOWER DELBY AREA)

$$(Q_p)_3 = (Q_p)_3 = 7500 \text{ cfs} \quad (y_3)_3 = 5.9'$$

d) APPROXIMATE STAGE BEFORE FAILURE,  $\frac{1}{2}$  FROM L.A. RESERVOIR.

$$Q_s = 240 \text{ cfs}$$

(i) 1<sup>ST</sup> REACH:  $(y_s)_1 = 2.2'$

(ii) 2<sup>ND</sup> REACH:  $(y_s)_2 = 2.7' \quad (y_c = 3.3') \quad (y_n = 11')$

(iii) 3<sup>RD</sup> REACH:  $(y_s)_3 = 0.9'$  (CAPACITY OF EXISTING CONDUIT IS REACHED)

e) RAISE IN STAGE  $\frac{1}{2}$  FROM L.A. RESERVOIR:

(i) 1<sup>ST</sup> REACH:  $(y_1)_1 = 5.7' \quad (\text{HIGH ST. AREA})$

(ii) 2<sup>ND</sup> REACH:  $(y_1)_2 = 7.2'$

(iii) 3<sup>RD</sup> REACH:  $(y_1)_3 = 5.0' \quad (\text{LOWER DELBY AREA})$

Project NON-FEDERAL DAMS INSPECTION Sheet D-13 of 14  
 Computed By RLU Checked By GMB Date 7/23/80  
 Field Book Ref. \_\_\_\_\_ Other Refs. CE #27-785-HA Revisions \_\_\_\_\_

### III) SELECTION OF TEST FLOOD.

#### 1) CLASSIFICATION OF DAM ACCORDING TO NED-ACE GUIDELINES.

a) SIZE. \*STORAGE (MAX)  $\approx 310 \text{ ACFT}$  ( $50 < S < 1000 \text{ ACFT}$ )  
 \*HEIGHT  $\approx 20.8'$  ( $H < 25 \text{ FT}$ )

\*STORAGE: SEE P. D-11; HEIGHT: SEE P. D-7 (DIKE #1:  $H_{DK} = 16.2'$  SEE P. D-8)

b) SIZE CLASSIFICATION: SMALL

b) HAZARD POTENTIAL: AS A RESULT OF THE P/L FAILURE ANALYSIS AND IN VIEW OF THE IMPACT THAT FAILURE OF UPPER ANSONIA RESERVOIR DAM/DIKES MAY HAVE ON THE POTENTIAL IMPACT AREAS (P. D-7), THE DAM IS CLASSIFIED AS HAVING:

HAZARD CLASSIFICATION: HIGH

c) TEST FLOOD. PMF = 1200 CFS

THIS SELECTION IS BASED ON THE RESULTS OF THE PREVIOUS ANALYSIS AND CLASSIFICATION.

Project NON-FEDERAL DAMS INSPECTION Sheet D-14 of 14  
 Computed By HLU Checked By GRB Date 7/23/80  
 Field Book Ref. \_\_\_\_\_ Other Refs. CE# 27-785-HA Revisions 11/12/80 HLU

### UPPER ANSONIA RESERVOIR DAM

#### IV) SUMMARY

1) TEST FLOOD = PMF  $\approx 1200$  cfs

(PARALLEL COMPUTATIONS HAVE BEEN MADE FOR  $\frac{1}{2}$  PMF  $\approx 600$  cfs AND ARE ALSO SUMMARIZED BELOW)

2) PERFORMANCE AT PEAK FLOOD CONDITIONS:

a) PEAK INFLOWS:  $Q_P = PMF \approx 1200$  cfs

$Q_P' = \frac{1}{2} PMF \approx 600$  cfs

b) PEAK OUTFLOWS:  $Q_B \approx 870$  cfs

$Q_B' \approx 310$  cfs

c) SPILLWAY CAPACITY: (SEE TABLE p. D-6)

d) PERFORMANCE:

i) AT TEST FLOOD: OVERTOPPED (?) 0.6' ABOVE LOW PT. @ DIKE #3 (WS. EL. 310.1 AK 6)

ii) AT  $\frac{1}{2}$  PMF: OVERTOPPED (?) 0.3' ABOVE LOW PT. @ DIKE #3 (WS. EL. 309.8 AK 6)

3) DOWNSTREAM FAILURE CONDITIONS:

a) PEAK FAILURE OUTFLOW:  $Q_P = 8600$  cfs (DIKE #1); (MAIN DAM:  $Q_P \approx 4100$  cfs)

b) FLOOD DEPTH IMMEDIATELY  $\frac{1}{2}$  FROM DAM:  $Y_0 \approx 6.9'$  (DIKE #1); (MAIN DAM:  $Y_0 \approx 9.1'$ )

c) CONDITIONS AT THE HIGH ST. AREA:

STAGE BEFORE FAILURE:  $Y_S \approx 2.2'$  ( $Q_S \approx 240$  cfs)

STAGE AFTER FAILURE:  $Y_3 \approx 7.9'$  ( $Q_3 \approx 7500$  cfs)

RAISE IN STAGE AFTER FAILURE:  $\Delta Y \approx 5.7'$

d) CONDITIONS AT THE INITIAL IMPACT AREA (LOWER SECTION OF DIBEY)

STAGE BEFORE FAILURE:  $Y_S \approx 0.9'$  ( $Q_S \approx 240$  cfs)

STAGE AFTER FAILURE:  $Y_3 \approx 5.9'$  ( $Q_3 \approx 7500$  cfs)

RAISE IN STAGE AFTER FAILURE:  $\Delta Y \approx 5.0'$

I

PRELIMINARY GUIDANCE  
FOR ESTIMATING  
MAXIMUM PROBABLE DISCHARGES  
IN  
PHASE I DAM SAFETY  
INVESTIGATIONS

New England Division  
Corps of Engineers

March 1978




MAXIMUM PROBABLE FLOOD INFLOWS  
NED RESERVOIRS

<u>Project</u>	<u>Q</u> (cfs)	<u>D.A.</u> (sq. mi.)	<u>MPF</u> cfs/sq. mi.
1. Hall Meadow Brook	26,600	17.2	1,546
2. East Branch	15,500	9.25	1,675
3. Thomaston	158,000	97.2	1,625
4. Northfield Brook	9,000	5.7	1,580
5. Black Rock	35,000	20.4	1,715
6. Hancock Brook	20,700	12.0	1,725
7. Hop Brook	26,400	16.4	1,610
8. Tully	47,000	50.0	940
9. Barre Falls	61,000	55.0	1,109
10. Conant Brook	11,900	7.8	1,525
11. Knightville	160,000	162.0	987
12. Littleville	98,000	52.3	1,870
13. Colebrook River	165,000	118.0	1,400
14. Mad River	30,000	18.2	1,650
15. Sucker Brook	6,500	3.43	1,895
16. Union Village	110,000	126.0	873
17. North Hartland	199,000	220.0	904
18. North Springfield	157,000	158.0	994
19. Ball Mountain	190,000	172.0	1,105
20. Townshend	228,000	106.0(278 total)	820
21. Surry Mountain	63,000	100.0	630
22. Otter Brook	45,000	47.0	957
23. Birch Hill	88,500	175.0	505
24. East Brimfield	73,900	67.5	1,095
25. Westville	38,400	99.5(32 net)	1,200
26. West Thompson	85,000	173.5(74 net)	1,150
27. Hodges Village	35,600	31.1	1,145
28. Buffumville	36,500	26.5	1,377
29. Mansfield Hollow	125,000	159.0	786
30. West Hill	26,000	28.0	928
31. Franklin Falls	210,000	1000.0	210
32. Blackwater	66,500	128.0	520
33. Hopkinton	135,000	426.0	316
34. Everett	68,000	64.0	1,062
35. MacDowell	36,300	44.0	825

MAXIMUM PROBABLE FLOWS  
BASED ON TWICE THE  
STANDARD PROJECT FLOOD  
(Flat and Coastal Areas)

<u>River</u>	<u>SPF</u> (cfs)	<u>D.A.</u> (sq. mi.)	<u>MPF</u> (cfs/sq. mi.)
1. Pawtuxet River	19,000	200	190
2. Mill River (R.I.)	8,500	34	500
3. Peters River (R.I.)	3,200	13	490
4. Kettle Brook	8,000	30	530
5. Sudbury River.	11,700	86	270
6. Indian Brook (Hopk.)	1,000	5.9	340
7. Charles River.	6,000	184	65
8. Blackstone River.	43,000	416	200
9. Quinebaug River	55,000	331	330

## ESTIMATING EFFECT OF SURCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES



STEP 1: Determine Peak Inflow ( $Q_{p1}$ ) from Guide Curves.

STEP 2: a. Determine Surcharge Height To Pass " $Q_{p1}$ ".

b. Determine Volume of Surcharge ( $STOR_1$ ) In Inches of Runoff.

c. Maximum Probable Flood Runoff In New England equals Approx. 19", Therefore:


$$Q_{p2} = Q_{p1} \times \left(1 - \frac{STOR_1}{19}\right)$$

STEP 3: a. Determine Surcharge Height and " $STOR_2$ " To Pass " $Q_{p2}$ "

b. Average " $STOR_1$ " and " $STOR_2$ " and Determine Average Surcharge and Resulting Peak Outflow " $Q_{p3}$ ".

# **MAXIMUM PROBABLE FLOOD PEAK FLOW RATES**

x 5 - NED DAM IDENTIFICATION  
 ⊗ 7' - TWICE SPF AT INDICATED SITES  
 DEC. 1977



## **SURCHARGE STORAGE ROUTING SUPPLEMENT**

**STEP 3: a. Determine Surcharge Height and  
"STOR<sub>2</sub>" To Pass "Q<sub>p2</sub>"**

**b. Avg "STOR<sub>1</sub>" and "STOR<sub>2</sub>" and  
Compute "Q<sub>p3</sub>".**

**c. If Surcharge Height for Q<sub>p3</sub> and  
"STOR<sub>avg</sub>" agree O.K. If Not:**

**STEP 4: a. Determine Surcharge Height and  
"STOR<sub>3</sub>" To Pass "Q<sub>p3</sub>"**

**b. Avg. "Old STOR<sub>avg</sub>" and "STOR<sub>3</sub>"  
and Compute "Q<sub>p4</sub>"**

**c. Surcharge Height for Q<sub>p4</sub> and  
"New STOR<sub>avg</sub>" should Agree  
closely**

## SURCHARGE STORAGE ROUTING ALTERNATE

$$Q_{p2} = Q_{p1} \times \left( 1 - \frac{\text{STOR}}{19} \right)$$


$$Q_{p2} = Q_{p1} - Q_{p1} \left( \frac{\text{STOR}}{19} \right)$$

FOR KNOWN  $Q_{p1}$  AND 19" R.O.


$Q_{p2}$

STOR

EL.



# "RULE OF THUMB" GUIDANCE FOR ESTIMATING DOWNSTREAM DAM FAILURE HYDROGRAPHS



**STEP 1:** DETERMINE OR ESTIMATE RESERVOIR STORAGE (S) IN AC-FT AT TIME OF FAILURE.

**STEP 2:** DETERMINE PEAK FAILURE OUTFLOW ( $Q_{p1}$ ).

$$Q_{p1} = \frac{8}{27} w_b \sqrt{g} Y_0^{3/2}$$

$w_b$  = BREACH WIDTH - SUGGEST VALUE NOT GREATER THAN 40% OF DAM LENGTH ACROSS RIVER AT MID HEIGHT.

$Y_0$  = TOTAL HEIGHT FROM RIVER BED TO POOL LEVEL AT FAILURE.

**STEP 3:** USING USGS TOPO OR OTHER DATA, DEVELOP REPRESENTATIVE STAGE-DISCHARGE RATING FOR SELECTED DOWNSTREAM RIVER REACH.

**STEP 4:** ESTIMATE REACH OUTFLOW ( $Q_{p2}$ ) USING FOLLOWING ITERATION.

A. APPLY  $Q_{p1}$  TO STAGE RATING, DETERMINE STAGE AND ACCOMPANYING VOLUME ( $V_1$ ) IN REACH IN AC-FT. (NOTE: IF  $V_1$  EXCEEDS  $1/2$  OF S, SELECT SHORTER REACH.)

B. DETERMINE TRIAL  $Q_{p2}$ .

$$Q_{p2}(\text{TRIAL}) = Q_{p1} \left(1 - \frac{V_1}{S}\right)$$

C. COMPUTE  $V_2$  USING  $Q_{p2}$  (TRIAL).

D. AVERAGE  $V_1$  AND  $V_2$  AND COMPUTE  $Q_{p2}$ .

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_{\text{avg}}}{S}\right)$$

**STEP 5:** FOR SUCCEEDING REACHES REPEAT STEPS 3 AND 4.

APRIL 1978

APPENDIX E

INFORMATION AS CONTAINED IN  
THE NATIONAL INVENTORY OF DAMS